BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer, Dasarahalli Division

D.T.S

NAME OF THE WORK: Construction of RCC drain in 19th, 21st cross roads at Ravindra Nagra in ward no. 13 Shettyhalli sub division

Sl. No	Description of work	Unit	Qty	Rate to be Quoted	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specifications and directions of engineer in charge of the work	Cum	527.10		
2	Removing B S Slab Drain And Stacking etc complete as per specifications and directions of engineer in charge of the work	~~Cum~~ Sqmt	677.70		
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 complete as per specifications and directions of engineer in charge of the work From Using Available coarse aggregates	Cum	59.80		
4	Remaining balance Qty Type Correct Le Bucy Specification	Cum	15.50		

Signature of the Contractor

Bruhat bengaluru mahanagara Pal...
Dasarahalli Division, Bengaluru-57

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner

5	Proveding and Laying plain reinforced cement concrete for side drains using M 20 nominul mix concrete with OPC cement 300kgs. With 20mm and down size ganite metal course aggregates @0.69cum and fine aggregates @0.43cum machine mixed,well compacted for walls and bottom including centring,shuttring,cost of materails, HOM of machinaries. Complete Excluding cost of steel asper MORTH Specification no1500,1700,2200. Wall And Bottom thickness 15cm complete as per specifications and directions of engineer in charge of the work	cum	180.72		
6	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per pecifications.Specification No. KBS 4.6.3, TMT bars Fe 500. complete as per specifications and directions of engineer in charge of the work	Tonne	10.84		
7	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications. and directions of engineer in charge of the work	sqm	373.50		

Number of Corrections: (2) (Two)

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

DTS Approved

ಕಾರ್ಯ ಪಥಯಂತರದು
ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

Executive Engineer
Dasarahalli Division
BBMP

Signature of the Contractor

Scanned by CamScanner